

## RFQ 2FY20 Vendor Question 13

1. For both Indoor training Open & Office Bldgs. The exterior wall type shows 3/4" plywood covering required please clarify the height. *The plywood would be the whole length of the wall. This will be the interior wall finish instead of using gypsum wall board. Plywood is only for the indoor open training building. The office has no plywood for the wall coving, it states to use 5/8" type x gypsum wall board.*