

RFQ 2FY20 Vendor Question 21

1. 2" Kingspan Optimo panels are specified on both the Indoor Training Open and Indoor Training Office along with R-19 batt insulation on the exterior wall type "B". Please confirm this is design intent as this exceeds required R value for building.

R-19 is the level of insulation required. R-13 insulation may be used if the 2" Kingspan Optimo Panel will bring the wall assembly up to a total of an R-19 rating.

2. Are the metal building columns to receive drywall and metal stud to hide them? Detail 3 per A2.0 on the Indoor Training Open appears to show this detail but is not labeled as such.

This is correct.

3. For both the Indoor Training Open and the Indoor Training Office, is the roof to be insulated using the insulated panels or vinyl backed insulation above ceiling?

The roof is to have r-19 with r-11s minimum insulation installed between and below structure.